

BoQ; PROPOSED PHASE 2 FENCING (MASONRY WALL)AT KAJIADO

Bill of Quantities For the Proposed Fence At Kajiado					Page 1
Bill No.	GENERAL PRELIMINARIES				Project:
Item No	Description	Units	Quantity	Unit Bid Rate (Ksh)	Amount Ksh
	<u>GENERAL PRELIMINARY</u>				
1.01	Allow contractual requirements, training levy with holding tax and other GoK statutes necessary to commence and proceed with the works to completion.	SUM	1		
1.02	Allow preliminaries to cover overheads, transport, security, storage, water for construction, power supply, clients safety requirements, "Contractors all Risks" and other insurances as required by the general Conditions of Contract, all temporary Works not covered elsewhere under specific items of the Bills of Quantities (Provisional Sum not to exceed 10% of Contract Sum)	SUM	1		
TOTAL CARRIED TO SUMMARY					

Bill of Quantities For the Proposed Fence At Kajiado

Page 2

Bill No.	EXCAVATIONS (Provisional) & STEELWORKS				Project:
tem No	Description	Units	Quantity	Unit Bid Rate (Ksh)	Amount Ksh
	<u>EXCAVATIONS (Provisional)</u>				
2.01	Excavate for foundation pillars bases size 1200x1200mm, averagely 1200mm deep.	CM	55		
2.02	Excavate for perimeter strip foundation size 600mm wide , averagely 1000mm deep.	CM	144		
2.03	Load and cart away surplus excavated materials from site and deposit as directed	CM	199		
2.04	Return and properly ram approved fill materials around foundations	CM	70		
	<u>CONCRETE (MIX ;1:2:4)</u>				
2.05	Concrete (1:2:4) mix 20mm max. aggregate size 1200x1200x500mm in pillar foundation bases.	CM	44		
2.06	Concrete (1:2:4) mix 20mm max. aggregate size in pillars size 400x400mm finish with fair face finish.	CM	30		
	<u>CONCRETE (MIX ;1:4:8)</u>				
2.07	Concrete (1:4:8) mix 20mm max. aggregate size in strip foundation bases.	CM	30		
	<u>WALLING</u>				
	<u>Natural quarry dressed masonry block walling in cement and sand (1:3) mortar</u>				
2.08	200mm Walling including hoop iron in every alternative course.	SM	600		
	<u>STEEL REINFORCEMENT</u>				
	<u>As described including cutting to lengths, bending, hoisting and fixing including all necessary tying wire and spacing blocks</u>				
3.01	8mm Ditto	Kgs	1150		
3.02	12mm Ditto	Kgs	1870		
TOTAL CARRIED TO SUMMARY					

Bill of Quantities For the Proposed Fence At Kajiado

Page 4

	SUMMARY	Project:
Item No	Description	Amount (Kshs)
	<u>SUMMARY</u>	
1	From Page 1	
2	From Page 3	
<u>SUMMARY</u>		
(A)	TOTAL OF BILLS	
(B)	ADD: Provisional Sum for Contingency {10% of A}	
(C)	SUB-TOTAL [(A) + (B)]	
(D)	ADD: Provision for Value Added Tax (VAT) {16% of (C)}	
(E)	BID PRICE [(C) + (D)] Form of Bid	(Carried Forward to